3310 HILL AVENUE • EVERETT, WASHINGTON 98201 • TELEPHONE (425) 259-6799 FAX (425) 259-4936 www.nctlinc.com

## AAMA/WDMA/CSA 101/I.S.2/A440-08 STRUCTURAL TEST REPORT

 $310-2338_{E0A0}$ 

**REPORT TO:** 

CUSTOM DESIGNED SYSTEMS 18315 PORTLAND AVENUE GLADSTONE, OR 97027

ORIGINAL REPORT NUMBER: ORIGINAL REPORT DATE:

310-2338 01/05/2012

MODEL/TYPE:

3100 SERIES 2489 X 1264 (98 X 50) SLOPE GLAZED SKYLIGHT

Professionals in The Science of Testing



# NATIONAL CERTIFIED TESTING LABORATORIES

3310 HILL AVENUE • EVERETT, WASHINGTON 98201 • TELEPHONE (425) 259-6799
FAX (425) 259-4936
www.nctlinc.com

#### AAMA/WDMA/CSA 101/I.S.2/A440-08 STRUCTURAL TEST REPORT SUMMARY

#### **RENDERED TO:**

#### CUSTOM DESIGNED SYSTEMS 18315PORTLAND AVENUE GLADSTONE, OR 97027

#### MODEL/TYPE: 3100 SERIES SLOPE GLAZED SKYLIGHT

TITLE	SUMMARY OF RESULTS			
Primary Product Designator	Class CW - PG70 2489 x 1264 (98 x 50) - Type SKG			
Air Infiltration/Exfiltration	$0.02 \text{ L/s/m}^2 (< 0.01 \text{ cfm/ft}^2)$ – Infiltration $< 0.01 \text{ L/s/m}^2 (< 0.01 \text{ cfm/ft}^2)$ – Exfiltration			
Water Penetration Resistance	720 Pa (20.00 psf)			
Design Pressure	3360 Pa (70.0 psf)			
Uniform Load Structural Test	5030 Pa (105.0 psf)			

Test Completion Date: 12/30/2011

Reference must be made to NCTL Report Number 310-2338<sub>E0A0</sub> dated 01/05/2012 for complete test sample description and data.

For National Certified Testing Laboratories:

Jim Clarke

Structural Performance Technician

REPORT TO: Custom Designed Systems

18315 Portland Avenue Gladstone, OR 97027

STARTING TEST DATE:

12/29/2011 12/30/2011

ENDING TEST DATE:

SPECIFICATION:

AAMA/WDMA/CSA 101/I.S.2/A440-08

DESCRIPTION OF SAMPLE TESTED

NAFS-North American Fenestration Standard/Specification for Windows, Doors and

Skylights.

PERFORMANCE CLASS: Class CW - PG70 2489 x 1264 (98 x 50) - Type SKG

MODEL/TYPE: 3100 Series Slope Glazed Skylight.

CONFIGURATION: OO

FRAME SIZE: 2489 mm (98") wide by 1264 mm (49 3/4") high.

FIXED DAYLIGHT OPENING: Each fixed lite opening measured 1175 mm (46 1/4") wide by 1175 mm (46 1/4") high

when measured from the interior.

FRAME TYPE: Extruded anodized aluminum.

JOINT CONSTRUCTION: All corners were mitered, sealed and multiple screw-connected with aluminum angle...

The intermediate vertical member was butt joined, sealed and multiple screwconnected to the head and sill extrusions via aluminum angle. A U-shaped aluminum extrusion was attached to the exterior face of the head, sill and jambs near the exterior-most edge. Self adhesive flashing tape was applied to the outer edge face of

each main frame member.

**GLAZING COMPONENTS:** 

OVERALL: 30 mm (1 3/16") nominal.

GLASS THICKNESS: One exterior pane of 8.0 mm nominal annealed.

One interior pane of 6.0 mm nominal annealed.

SPACER TYPE/SIZE: 16 mm (5/8") nominal aluminum.

GLAZING SYSTEM: All glass was set on blocks, bedded against a preset glazing gasket on the interior side

of the glazing pocket and retained on the exterior with an aluminum pressure bar with

an anodized aluminum cover.

WEATHERSTRIP: None.

WEEP SLOTS: None.

INSTALLATION DESCRIPTION: The skylight was installed in a 51 x 203 mm (2x8) wood buck, built tight around the

perimeter. A  $32 \times 19$  mm (1 1/4" x 3/4") wood stop was screw-connected around the perimeter of the interior and exterior of the buck at approximately 203 mm (8") on center using #8 x 32 mm (1 1/4") washer head screws. The exterior face of the

skylight was sealed with silicone sealant to the test buck.

#### **TEST RESULTS**

### 5.3.2 AIR LEAKAGE RESISTANCE AT 75 PA (1.6 PSF).

AS	TM	E283	-04

Maximum Permanent Set

Maximum Allowed

span.

0.3% for CW Rating.

The Tested Specimen Meets Or Exceeds the P	$ft^2 = 33.86$				
AAMA/WDMA/CSA 101/I.S.2/A440-08 for Air	$M^2 = 3.15$				
Maximum Allowable. Infiltration	1.5	L/s/m <sup>2</sup>	0.3	CFM/ft²	
Optional Information at 1.6 psf					
Total L/S (CFM)	0.06	L/S	0.13	CFM	
Infiltration Rate	0.02	L/s/m <sup>2</sup>	< 0.01	CFM/ft²	
Exfiltration					
Optional Information at 1.6 psf					
Total L/S (CFM)	< 0.01	L/S	< 0.01	CFM	
Infiltration Rate	< 0.01	L/s/m <sup>2</sup>	< 0.01	CFM/ft <sup>2</sup>	
No Leakage after 4 cycles of 5 minutes at	720	pa	15.00	psf	
No Leakage after 4 cycles of 5 minutes at	720	ра	15.00	psf	<del></del>
5.3.4.2 UNIFORM LOAD DEFLECTION	AT DESIG	N PRESSURI	<u>c.</u>		
ASTM E330-02					
No Damage After Positive	3360	pa	70.0	psf	
No Damage After Negative	3360	pa	70.0	psf	
Measured Deflection Positive	2	mm	0.063	inches	
Measured Deflection Negative	2	mm	0.061	inches	
Maximum Allowed (L/175)	7	mm	0.284	inches	·
5.2.4.2 VINVEODA LOAD CERVICEVIDA L	mr.cm				
5.3.4.3 UNIFORM LOAD STRUCTURAL ASTM E330-02	<u>1ES1.</u>				
No Damage After Positive	5030	pa	105.0	psf	
No Damage After Negative	5030	pa	105.0	psf	

< 1 mm

1 mm

Note: Deflection and Permanent Set Measurements taken on the intermediate vertical member with a 1264 mm (49 3/4")

0.002 inches

0.024 inches

All tests were conducted at NCTL, 3310 Hill Avenue, Everett, WA 98201.

Detailed assembly drawings showing wall thickness of all members, corner construction and hardware application have been compared to the sample submitted and are attached to this report.

The results were secured by using the designated test methods and they indicate compliance with the performance requirements of the referenced specification. A copy of this report has been forwarded to the Administrator of the Certification Program. This report does not constitute certification of this product, which may only be granted by the Administrator.

This report is the joint property of National Certified Testing Laboratories and the Client to whom it is issued. Permission to reproduce this report by anyone other than National Certified Testing Laboratories and the Client must be granted in writing by both of the above parties. This report may not be reproduced except in its entirety. The results in this report are actual tested values and are applicable to the sample tested only, using the components and construction methods described herein.

Jeffrey M. Douglas Lab Manager

Jim Clarke

Structural Performance Technician